

JRS RETAIL SERVICES

Commercial Retail Construction / Retail Remodel Subcontractor

QUOTE

JRS-LC-2026-0629

June 29, 2026

PREPARED FOR LensCrafters
PROJECT LensCrafters Clinic Remodel (Labor Only)
STORE # 0290
LOCATION San Bernardino, CA
PREPARED BY Richard Bodington / JRS Retail Services
PHONE 832-361-6551

1. PROJECT SUMMARY

Labor-only remodel of an approximately 6,000 SF LensCrafters clinic (back room ~1,000 SF; sales, offices and remaining areas ~5,000 SF). JRS provides labor, equipment, travel and lodging only; all materials, fixtures, ceiling tile, flooring and paint are furnished by others.

Basis: standard 10-hour production shifts; medical-retail / occupied-store conditions with night work for customer-facing areas (premium applied); 4-person crew (incl. lead) over an estimated 7-9 shifts.

2. SCOPE OF WORK INCLUDED (LABOR ONLY)

- Light interior demo and prep across clinic (~6,000 SF), debris consolidated to one point.
- Wallcovering removal where applicable, then skim coat, sand and paint prep (no painting over wallcovering).
- Patch, prime and two-coat retail paint of walls in sales, offices and back room.
- Ceiling tile replacement labor; tiles to match existing exactly (tiles by others).
- Flooring installation labor (LVT/resilient or carpet tile, client material), incl. floor prep/adhesive scrape; flooring under cabinets where possible.
- Fixture / millwork install and remove-and-reset labor as directed.
- Final detailed clean, dust control throughout, and punchlist completion to client punchlist angles.

3. ESTIMATE BREAKDOWN (LABOR-ONLY SELL RATES)

#	DESCRIPTION	QTY	UNIT	UNIT PRICE	LINE TOTAL
1	Interior demo & prep, occupied store	6,000	SF	\$3.50	\$21,000
2	Wallcovering removal + skim/sand prep	2,500	SF	\$3.25	\$8,125
3	Patch + two-coat retail paint, walls	9,000	SF	\$1.75	\$15,750
4	Ceiling tile replacement (labor)	6,000	SF	\$1.75	\$10,500
5	Floor prep / adhesive scrape	6,000	SF	\$1.50	\$9,000
6	LVT/resilient flooring install (labor)	6,000	SF	\$4.00	\$24,000
7	Fixture/millwork R&R; (allowance)	1	LS	\$6,500	\$6,500
8	Final clean + punchlist (allowance)	1	LS	\$4,500	\$4,500

4. TRAVEL / LODGING / EQUIPMENT (ALLOWANCES)

Out-of-town mobilization (allowance)	\$1,250
Lodging allowance (4 rooms x ~8 nights @ \$110+tax)	\$4,400
Per diem / M&IE; (4 workers x ~8 days @ \$68)	\$2,176

Scissor lift allowance (~8 days @ \$250)	\$2,000
Lift delivery/pickup allowance	\$500

5. TOTAL PRICE

Labor subtotal	\$99,375
Travel / lodging / equipment	\$10,326

BUDGETARY LABOR-ONLY TOTAL

Approximately \$105,000 - \$122,000

6. ASSUMPTIONS

- Labor only; 10-hour production shifts.
- All materials, fixtures, ceiling tile, flooring and paint furnished by client/GC unless listed.
- Quantities based on the ~6,000 SF breakdown provided; not yet field-verified.
- Site access provided during scheduled hours; merchandise and sensitive clinic/OD equipment moved/protected by store.
- Debris consolidated by JRS; haul-off/dumpster by others unless listed.
- Medical-retail protocol assumed (dust control, exact ceiling tile match, no painting over wallcovering, punchlist-angle photos).

7. EXCLUSIONS

- All materials unless specifically listed.
- Permits, taxes (unless required), engineering and design.
- Dumpster / haul-off unless listed.
- Licensed electrical, plumbing, HVAC, fire alarm, sprinkler and low-voltage work.
- Disconnection/reconnection of OD or clinic equipment (requires authorized OD tech).
- Merchandise moving, hazmat, asbestos/mold/lead/environmental abatement.
- Structural modifications, unforeseen/hidden conditions, repairs to existing damage unless listed.
- After-hours mall/security fees unless listed; extra mobilizations by others; work outside listed scope.

8. CLARIFICATIONS / OPEN ITEMS

- Confirm store number and project location/state (affects regional pricing, travel, code/ADA verification).
- Confirm occupied vs. vacant and required work hours (night work).
- Confirm flooring type and whether floor prep/scrape is required.
- Confirm fixture/millwork count for Line 7.
- Confirm dumpster/haul-off and debris responsibility.
- Confirm whether OD/clinic equipment disconnection is required.

9. TERMS

- Quote valid 15 days from date above.
- Work outside the listed scope handled via change order.
- Schedule subject to crew availability and site readiness; delays caused by others may add charges.
- Payment terms: per subcontract agreement.

10. AUTHORIZATION

Accepted by: _____

Name / Title: _____

Date: _____

COMPLIANCE NOTE: Any altered accessible route or clearances should be verified against ADA 2010 Standards. The exact ADA section must be verified manually against the official text and local code adoption once the project location is confirmed.